

ABSTRACT

An actual run-up ramp is measured for an internal combustion engine-generator unit (1) during a starting process. The actual run-up ramp is then set as the set run-up ramp. In this way, the closed-loop control of the internal combustion engine-generator unit (1) adapts itself to the on-site conditions.